



CITY OF TEMPLE REQUEST FOR SEALED BIDS FOR ASPHALT CONTRACT 1-2023

The City of Temple is soliciting sealed bids from qualified paving companies for the following Subdivision streets. Webster Lake Subdivision, Arbor Landing Subdivision, and Lakeland Park Subdivision. Please use the bid tab to complete your proposals.

The deadline for receipt of sealed bids by the City of Temple is Tuesday, November 28, 2023. Bids will be opened on this date at 2:00pm, at Temple City Hall, 240 Carrollton Street. The mailing address is either 240 Carrollton Street Temple, GA 30179 or Post Office Box 160 Temple, GA 30179.

Webster Lake includes the following scope of work.

The total linear footage of the FINAL TOPPING is 2,700 linear feet with an average width of 24 feet. There are 2 cul-de-sacs with an average radius of 40 feet. This site can be seen by reviewing plans for this subdivision, q-public, Google Earth, or through on-site observation.

Full depth milling is to be done throughout 50% of this site and includes installation of Recycled Asphalt SP 19MM Binder at a minimum of 2 inches in thickness, include the milling in the cost of the 19.5MM asphalt. A 1-inch final topping of Recycled Asphalt SP 9.5MM is to be placed throughout the entire site.

ALL MILLINGS MUST BE RETURNED TO THE CITY OF TEMPLE PUBLIC WORKS DEPARTMENT AT 155 MONTGOMERY STREET TEMPLE, GA 30179.

For identification purposes: Webster Lake Subdivision is located at the end of Old Bremen Rd in Temple, GA.

Arbor Landing includes the following scope of work.

The total linear footage of the FINAL TOPPING is 1,950 linear feet with an average width of 24 feet. There are 4 cul-de-sacs with an average radius of 40 feet. This site can be seen by reviewing plans for this subdivision, q-public, Google Earth, or through on-site observation.

Patching is required at various locations throughout this site and includes the installation of Recycled Asphalt SP 19MM Binder at a minimum of 2 inches in thickness, include the milling in the cost of the 19.5MM asphalt. A 1-inch final topping of Recycled Asphalt SP 9.5MM is to be placed throughout the entire site. **ALL MILLINGS MUST BE RETURNED TO THE CITY OF TEMPLE PUBLIC WORKS DEPARTMENT AT 155 MONTGOMERY STREET TEMPLE, GA 30179.**

For identification purposes: Arbor Landing Subdivision is located off Center Point Road.

Lakeland Park includes the following scope of work.

Milling and patching at various locations throughout the site using Recycled Asphalt SP 19.5MM at a minimum of 2 inches in thickness, include the milling in the cost of the 19.5MM asphalt.

This site can be seen by reviewing plans for this subdivision, q-public, Google Earth, or through on-site observation. **ALL MILLINGS MUST BE RETURNED TO THE CITY OF TEMPLE PUBLIC WORKS**

DEPARTMENT AT 155 MONTGOMERY STREET TEMPLE, GA 30179.

For identification purposes: Lakeland Park Subdivision is located off Bar J Road.

The undersigned bidder hereby declares that he has carefully examined the information contained herein. All prices must include labor, materials, and equipment to complete the project.

Factors in the City Council's selection of the company to perform this work will include the price, scope of work in repairing and then resurfacing these streets, and the timeline for completing the work.

Questions should be directed to Public Works Director Josh Smith by email at, jsmith@templega.us or by phone at, 678-699-3785.

Bid Tab

Description Webster Lake	Tons	Unit Price
FD Milling Recycled ASPH 19MM	400 tons	
Recycled ASPH SP 9.5MM	650 tons	
Description Arbor Landing	Tons	Unit Price
Patching Recycled ASPH 19MM	140 tons	
Recycled ASPH 9.5 MM	450 tons	

Description Lakeland Park	Tons	Unit Price
Patching Recycled ASPH 19.5MM	250 Tons	

All asphalt mixes shall meet the current GDOT Specifications.