

ADDENDUM NO. ONE

TO

**BID DOCUMENTS, CONTRACT DOCUMENTS,
CONSTRUCTION SPECIFICATIONS AND DRAWINGS**

FOR

**WATER SYSTEM IMPROVEMENTS
E. JOHNSON AND SAGE STREET WATER LINES**

FOR THE

CITY OF TEMPLE, GEORGIA

PROJECT NO. 222590

Bids Received Until Thursday, November 16, 2023 @ 2:00 p.m.

ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY INSERTING ITS NUMBER IN THE PROPOSAL. FAILURE TO DO SO MAY SUBJECT BONA FIDE BIDDERS TO DISQUALIFICATION. THIS ADDENDUM FORMS A PART OF THE PROJECT DOCUMENTS; IT MODIFIES THEM AS FOLLOWS:

November 13, 2023



BID DOCUMENTS

Refer to Proposal, Page P-4.

Replace Page P-4 with the enclosed Page P-4(A1)

[Directions: Staple the revised sheet to the existing sheet or replace them in the document]

RESPONSE TO BID QUESTIONS

1. Are Carrolton Avenue and Tallapoosa Street (both crossing) to be open cut?

They can be open cut or free bore.

2. If contaminated soils are encountered in old gas station parking lot, who will be responsible to remove?

The contractor will be responsible for removal. An extra work item is added to the proposal for this.

3. Does anyone know if tanks at gas station are out of running line or if they are deep enough to cross?

A subsurface investigation has not been performed. (Section 1.07)

4. Will railroad flagger be required?

The project has been permitted by Norfolk Southern and does not require a flagger because the railroad will not be crossed.

5. Who will locate camera wiring at school?

The contractor is required to locate wire. (Section 4.13)

6. Will the tie in at school be done after hours?

Yes, or during a school holiday.

7. On the NW corner of intersection at Tallapoosa Street and James Street, there is a power meter and some cut offs there. Will it be located, if so, by whom? It will be close to running line.

The contractor is required to locate wire. (Section 4.13)

8. Has an easement been acquired for bore pit across Church Street?

Not at this time, the Engineer will work with City to obtain the temporary construction easement.

9. Is there an option of free bore in the area in front of the funeral home to preserve large hardwood trees?

Yes

10. Please advise the older tree beside the driveway at 441 Sage Street.

The alignment can be adjusted to avoid the tree.

11a. Is Typical Installation in Pavement Detail on Sheet 10 of 15 to be used in roadways, driveways and parking lot areas?

Yes

11b. Is this the only acceptable method?

Yes

END OF ADDENDUM NO. ONE

CITY OF TEMPLE, GEORGIA

WSI - E. JOHNSON AND SAGE STREET WATER LINES

ITEM					UNIT PRICE	TOTAL PRICE
NO.	QTY.	UNIT	DESCRIPTION			
13.			FREE BORE (>50' in addition to pipe)			
a.	2	EA	10"			
Subtotal Items 1 through 13, inclusive, the amount of:						\$

EXTRA WORK, IF ORDERED BY ENGINEER

ITEM					UNIT PRICE	TOTAL PRICE
NO.	QTY.	UNIT	DESCRIPTION			
14.	100	CY	CRUSHED STONE STABILIZATION (Includes Excavation and Removal of Unsuitable Materials and Installation of Crushed Stone).			
15.	80	CY	CONTAMINATED SOILS (Includes Removal of Contaminated Soils, Disposal of Contaminated Soils in Compliance with EPD Regulations and Installation of Selected Backfill).			
Subtotal, Item 14-15 inclusive, the amount of:						\$

TOTAL AMOUNT BID, ITEMS 1 THROUGH 15, INCLUSIVE, THE AMOUNT OF:

_____ **DOLLARS** (\$ _____)

The Bidder further proposes and agrees hereby to commence work under contract, with adequate force and equipment, on a date to be specified in a written order of the Engineer, and shall fully complete all work thereunder within the consecutive calendar days set forth in the Contract Agreement.